# DIVISION 09 — FLOORING

Architectural & Technical Description

Scope of Work

This division encompasses the complete installation of flooring systems for the TownePlace Suites hotel project, covering a total net floor area of 12,850 square feet. The scope includes luxury vinyl plank (LVP) flooring totaling 8,920 SF, ceramic and porcelain tile installations covering 1,680 SF, commercial-grade carpet systems spanning 2,250 SF, and comprehensive substrate preparation including floor leveling compound application across the entire project area. The work includes all transition strips, grout and sealer applications, carpet padding, and substrate preparation materials. All flooring installations are calculated using net floor area methodology with room dimensions minus wall thickness deductions, ensuring accurate material quantities and labor estimates.

Materials & Finishes

The flooring specification includes 5mm luxury vinyl plank flooring at $2.85 per square foot material cost, designed for high-traffic hospitality environments in guest rooms, corridors, lobby, and common areas. Ceramic tile systems utilize 12"×12" tiles at $3.50 per square foot for standard bathrooms and utility areas, while premium 24"×24" porcelain tiles at $5.20 per square foot are specified for pool areas, pool restrooms, and high-traffic wet areas requiring enhanced durability and slip resistance. Commercial-grade carpet at $2.40 per square foot with 8-pound density carpet pad at $0.55 per square foot provides comfort and acoustic control in community rooms and buffet areas. Transition strips at $4.50 per linear foot ensure seamless material changes across 485 linear feet of boundaries.

Installation & Application

Installation methodology incorporates 10% material wastage factors for primary flooring materials and 5% for accessories, accounting for cutting waste, pattern matching, and field conditions. Labor costs range from $1.20 per square foot for carpet installation to $5.50 per square foot for porcelain tile work, reflecting the technical complexity and precision required for each system. Tile installations include comprehensive substrate preparation with mortar bed systems at $1.10 material cost and $1.80 labor cost per square foot, ensuring proper substrate stability and moisture protection. Grout and sealer applications at $0.30 material and $0.45 labor per square foot provide long-term durability and maintenance characteristics essential for hospitality environments.

Surface Preparation

Floor leveling compound application covers the entire 12,850 square feet at $0.45 material and $0.55 labor per square foot, addressing subfloor irregularities and ensuring proper substrate conditions for all flooring systems. This comprehensive preparation includes moisture testing, crack repair, and surface profiling to achieve the flatness tolerances required for luxury vinyl plank and tile installations. The 5% wastage factor for leveling compound accounts for varying substrate conditions and application thickness requirements across different areas of the hotel.

Drawings & Notes Reference

Quantity calculations are based on architectural drawing A1.01 at 3/32" = 1'-0" scale, with building dimensions of 244'-6" × 72'-7" overall footprint. The estimate identifies 15 guest rooms including studios, one-bedroom, and king units, plus pool area, fitness room, and community areas. Net floor area calculations assume 85% of gross room area to account for wall thickness, with finish types assigned per architectural finish schedule and room labeling systems.